START

₩.

JUN 0 1 1992 PNGINEERING DATA TRANSMITTAL

Page 1 of <u>/</u> 1. EDT 157786

| 2. To: (Receiving Organization) Distribution | 3. From: (Originating Organization) 100 Area Remedial Investigations | 4. Related EDT No.: N/A |
|---|---|---|
| 5. Proj./Prog./Dept./Div.: 100-FR-3 Groundwater Operable Unit | 6. Cog. Engr.: J. W. Roberts | 7. Purchase Order No.: N/A |
| 8. Originator Remarks: Release to file | 7-12.5 | 9. Equip./Component No.: |
| , | 23 AECF 1992 193 | 10. System/Bldg./Facility: N/A |
| 11. Receiver Remarks: | 1992 (100 EST) 1992 (100 EST | 12. Major Assm. Dwg. No.: N/A |
| | TONICO TO | 13. Permit/Permit Application No.: N/A |
| | SESSE ACCUSE SIND SOLUTION OF SIND SIND SOLUTION OF SIND SOLUTION OF SIND SIND SIND SIND SIND SIND SIND SIND | 14. Required Response Date: March 25, 1992 |

| | | | | | | -0101 | | | [] | ar Cir E | J, 1992 | |
|---------------------------|------------|-------------|--------------------------------------|---|------------------------|---|--|--|--|-----------------------------------|---|-----------------------------------|
| 15. | ***** | | | DATA | TRANSMITTE | D | | ···· | (F) | (G) | (H) | (1) |
| (A) Item No. | (8) | Document/Da | awing No. | (C) Sheet No. | (D) Rev. No. | (E) Title or Description of Data Transmitted | | | Impact Level | Reason for Trans- mittal | Origi- nator Dispo- sition | Receiv- er Dispo- sition |
| 1 | WHC- | SD-EN-A | NP-089 | | 0 | Description of Work for the 100-FR-3 Groundwater Operable Unit | | | 369 | 3 | 1 | 1 |
| | ļ | | | | | | | | | <u> </u> | | |
| | <u> </u> | | | | <u></u> | <u> </u> | · | | | <u></u> | | |
| 16. | mpact Le | val (F) | | Reason fo | r Transmittal | | Y | | Dispositio | n (H) & (I) | | |
| | , or 4 (se | | Approval Release Information | 4. Review 5. Post-F in 6. Dist. (| leview Receipt Ackn | | | 1. Approved 2. Approved w/co 3. Disapproved w/ | mment f | . Revièwec | i no/comměr i w/comměr cknowledge | ıt |
| (G) | (H) | 17. | | | | | DISTRIBUTION FROM THE PROPERTY OF THE PROPERTY | • • | | | (0) | (14) |
| Rea- son | Disp. | (J) Nan | | | Date (M) M | | (J) Na | me (K) Signat | ure (L) Daté | (M) MsIN | Red éor | 1 DIED. |
| 4 | 1 | | J. W. Rober | | <u> </u> | 16/92 | H4-5 | 55 | | | | |
| 4 | 1 | | . R. P. Henc | | 11 3/1 | 7/92 | 44-5 | 55 | | | | |
| 4 | 1 | QA G. S. | Corrigan 🕤 | Jan Cor | hear 34 | 792 | H4- | 16 | | | <u> </u> | |
| | | Safety | | | , | | | | | | | |
| | | Env. | | | | | | | | | | |
| | | | | | | | | | · | | | |
| | | | | | | | <u> </u> | | | | | |
| 18. Signatu Origina | J. / Et | Let 5/2 | | zed Represent elving Organiz | | | ognizant/Proje | | 21. DOE A Ltr. [] Approv [] Approv [] Disapp | No. ed ed w/comm | nents | ed) |

| 2. Title DESCRIPTION OF WORK FOR THE 100-FR-3 GROUNDWATER OPERABLE UNIT | 3. Number WHC-SD-EN-AP-089 | 4. Rev No. |
|---|---|------------|
| 5. Key Words APPROVED FOR 100-FR-3 DESCRIPTION OF WORK PUBLIC RELEASE GROUNDWATER OPERABLE UNIT | 6. Author Name: J. W. ROBERTS Signature Organization/Charge Code 8 | 1221/PH1AA |

7. Abstract


This description of work details the field activities to be conducted for the 100-FR-3 Operable unit and will serve as a field guide for those performing the work.

8. PURPOSE AND USB OF DOCUMENT - This document was prepared for use within the U.S. Department of Energy and its contractors. It is to be used only to perform, direct, or integrate work under U.S. Department of Energy contracts. This document is not approved for public release until reviewed.

PATENT STATUS - This document copy, since it is transmitted in advance of patent clearance is made available in onfirence solely for use in performance work under contract with the U.S. Department of Energy. This document is not to be sublished nor its contents otherwise disseminated or used for purposes other than specified above before patent approval for such release or use has been secured, upon request, from the Patent Counsel / U.S. Department of Energy Field Office, Richland, WA.

DISCLAIMER - This report was prepared as an account of work sponsored by an agency of the United States Government. Weither the United States Government nor any agency thereof, nor any of their employees, nor any of their contractors, subcontractors or their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or any third party's use or the results of such use of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof or its contractors or subcontractors. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

10. RELEASE STAMP



9. Impact Level 3 🛇

WHC-SD-EN-AP-089, Rev. 0

CONTENTS

| 1.0 | SCOPE OF WORK | 1 |
|-------------|--|-------------|
| 2.0 | GENERAL REQUIREMENTS | 1 |
| 3.0 | SAMPLING AND FIELD ACTIVITIES 3.1 SOIL SCREENING 3.2 GEOLOGIC SAMPLING 3.3 SOIL SAMPLING (PHYSICAL PROPERTY) 3.4 ANALYTICAL SAMPLING 3.5 GEOPHYSICAL LOGGING 3.6 AQUIFER TESTING | 7 |
| 4.0 | QUALITY ASSURANCE/QUALITY CONTROL REQUIREMENTS | 8 |
| 5.0 | SCHEDULE | 8 |
| 6.0 | CHANGES TO THE DESCRIPTION OF WORK | 9 |
| 7.0 | REFERENCES | 9 |
| ATTAC | HMENT | |
| I | 100-FR-3 DESCRIPTION OF WORK PROJECT CHANGE FORM | l I |
| FIGUR | E | |
| 1 | Location of Wells in 100-FR Area | 2 |
| TABLE: | S | |
| 1 2 3 | Well Depths and Sampling Information | 5 6 7 |

C

N

9

1.0 SCOPE OF WORK

This description of work details the field activities associated with cable tool drilling of groundwater wells in the 100-FR-3 Operable Unit (Task 6) and will serve as a field guide for those performing the work. It should be used in conjunction with the Remedial Investigation/Feasibility Study Work Plan for the 100-FR-3 Operable Unit, Hanford Site, Richland, Washington (DOE/RL 1991) for general investigation strategy and with Environmental Investigations and Site Characterization Manual (WHC 1988c) for specific procedures. Well locations are shown on Figure 1.

The coordinates used on Figure 1 are by USGS (1983). All wells on the map are prefixed with a 199, but the prefix has been dropped for clarity.

2.0 GENERAL REQUIREMENTS

2.1 HEALTH AND SAFETY

10

1

-

9

All personnel working to this description of work will have completed the 40-h Hazardous Waste Site Worker training program and will perform all work in accordance with the following:

- WHC-EP-0383, Environmental Engineering, Technology, and Permitting Function Quality Assurance Program Plan (WHC 1990)
- WHC-CM-4-10, Radiation Protection (WHC 1988d)
- WHC-IP-0692, Health Physics Procedures Manual (WHC 1991b)
- WHC-CM-4-11, ALARA Program (WHC 1988a)
- WHC-CM-4-3, Industrial Safety Manual, Vol. 1 through 3 (WHC 1987)
- WHC-CM-7-5, Environmental Compliance Manual (WHC 1988b)
- WHC-CM-7-7, Environmental Investigations and Site Characterization Manual (WHC 1988c)
- WHC-SD-EN-SAD-002, Rev 0, 100 Area Low Hazard Characterization Activities Safety Assessment (Taylor 1991)
- Site-specific health and safety plan/job safety analysis.




Figure 1. Location of Wells in 100-FR Area.

2.2 PREREQUISITES

Each item on the Drilling Planning Form (EII 6.7, Resource Protection Well and Test Borehole Drilling) (WHC 1988c) will be signed and dated by the cognizant engineer or field team leader prior to the start of work. A readiness review, if required will be conducted according to EII 1.13, Readiness Review (WHC 1988c). In addition, all field work will be conducted in accordance with Generic Well Specification (WHC 1991a).

3.0 SAMPLING AND FIELD ACTIVITIES

3.1 SOIL SCREENING

All samples and cuttings will be field screened for evidence of volatile organics and radionuclides (Section 5.1.6.2.3 of the 100-FR-3 work plan) (DOE/RL 1991). Volatiles will be screened by the field geologist using an organic vapor monitor (OVM) that will be used, maintained, and calibrated consistent with EII 3.2, Health and Safety Monitoring Instruments (WHC 1988c) and EII 3.4, Field Screening (WHC 1988c). Radionuclide screening will be performed by the field geologist per EII 3.4, Field Screening (WHC 1988c). The field geologist will record screening results in the borehole log (EII 9.1, Geologic Logging) (WHC 1988c).

The action level for radionuclide screening is twice background. The action level for volatile organic screening is 5 ppm above background. Prior to initiating drilling, determine a one time instrument background reading using the above instruments at the background site located on Figure 1. Instrument background will be measured on freshly disturbed surface soil, holding the instruments less than 1 in. from the soil. The field geologist will record the background levels in the borehole log per EII 9.1, Geologic Logging (WHC 1988c) prior to the start of drilling.

3.2 GEOLOGIC SAMPLING

Geologic samples will be taken at 5-ft intervals for each hole and at major stratigraphic changes for the preparation of borehole logs, per Section 5.1.6.2.3 of the 100-FR-3 work plan (DOE/RL 1991) and EII 9.1, Geologic Logging (WHC 1988c). The field geologist shall archive the nonradioactive geologic samples per EII 5.7A, Hanford Geotechnical Sample Library Control (WHC 1988c).

At the completion of each groundwater well two composite samples will be collected (from unsaturated sediments): one from archive samples in the top half of the well and one from archive samples in the bottom half. An equal volume will be taken from each archive sample, composited in a stainless steel bowl, and placed in a 500-ml glass bottle. Each composite sample will be analyzed for Gamma Spec only, as a check on the radiation detection instrument. Results will be recorded in the borehole log.

All waste generated during drilling activities will be handled according to EII 4.2, Interim Control of Unknown, Suspected Hazardous and Mixed Waste (WHC 1988a). (A CERCLA-specific EII is in preparation and will be used in lieu of EII 4.2 when issued.)

3.3 SOIL SAMPLING (PHYSICAL PROPERTY)

Collect four samples for physical property analysis per Section 5.1.5.3 of DOE/RL (1991) and EII 5.2, Appendix B, Soil and Sediment Sampling (WHC 1988c) from each of the following wells: 199-F5-43B, 199-F5-48, and 199-F7-3. Samples that do not meet the physical properties testing lab radiological acceptance criteria (anything > background) will not be collected for physical property testing. Alternate wells will be 199-F5-43A, 199-F5-47, and 199-F8-3.

The goal for selecting physical property samples is to collect two samples between the ground surface and the capillary fringe, (one near the surface and one between the surface and capillary fringe), one at the capillary fringe, and one within the saturated zone. The field geologist must use professional judgement to select samples that are representative of the principle soil types that can be sampled with the split-spoon sampler. One 6-in. sleeve, one moisture tin, and one bag (approximately 10 lb) will be collected. The field geologist will record the selected samples in the borehole log per EII 9.1, Geologic Logging (WHC 1988c).

These samples will be analyzed for the following parameters using American Society for Testing and Materials (ASTM) methods. Bulk density will be calculated. Kunsat will be both measured and calculated, for comparative purposes.

- Bulk density
- Particle Size Distribution (ASTM D422-63)
- Moisture Content (ASTM D2216)
- Moisture Retention (ASTM D2325-68, D3152-72)
- Saturated Hydraulic Conductivity (K_{sat}) (ASTM D2434-68) Unsaturated Hydraulic Conductivity (K_{unsat}) at 10% moisture content after full saturation.

Data collected from these analyses will be stored in the 100-FR-3 project files.

3.4 ANALYTICAL SAMPLING

3.4.1 Soil

S

O

Collect analytical soil samples in all wells except those listed below per Section 5.1.6.2.3 of the 100-FR-3 work plan (DOE/RL 1991) and EII 5.2, Appendix B, Soil and Sediment Sampling (WHC 1988c). Collect these at 10 ft above the expected groundwater, one 5 ft above and one 5 ft below the groundwater. In addition, if screening values (including borehole cuttings and geologic samples) exceed screening action levels, collect analytical samples with a split-spoon sampler at 5-ft intervals until either: 1) two

consecutive screening values fall below the screening action limits outlined above or 2) until 5 ft below groundwater.

Unless screening action levels are exceeded, only one analytical soil sample will be taken in well 199-F5-43B, at the bottom of the unconfined aquifer. If additional samples are required, they will be collected by the screening criteria described above and recorded in the borehole log (EII 9.1, Geologic Logging) (WHC 1988c).

Prior to drilling into the confined aquifer, the integrity of the well seal will be tested according to the test plan written for 300-FF-5 (EMO-1029, AD-940).

Estimated depths, screened intervals, and samples to be taken are shown on Table 1.

| Well number | Est. depth (ft) | Design type | Est. screened interval (ft) | Physical prop samples |
|-------------|-----------------|-------------|-----------------------------|--------------------------|
| 199-F6-1 | 60 | shallow | 55 - 75 | no |
| 199-F5-42 | 45 | shallow | 40 - 60 | no |
| 199-F5-43A | 45 | shallow | 40 - 60 | no |
| 199-F5-43B | 300 | deep | 290 - 300 | yes (4) |
| 199-F5-44 | 45 | shallow | 40 - 60 | no |
| 199-F5-45 | 42 | shallow | 37 - 57 | no |
| 199-F5-46 | 40 | shallow | 35 - 55 | no |
| 199-F5-47 | 60 | shallow | 55 - 75 | no |
| 199-F5-48 | 60 | shallow | 55 - 75 | yes (4) |
| 199-F8-3 | 48 | shallow | 43 - 63 | no |
| 199-F4-1 | 45 | shallow | 40 - 60 | no |
| 199-F1-2 | 60 | shallow | 55 - 75 | no |
| 199-F7-3 | 34 | shallow | 29 - 49 | yes (4) |
| 199-F8-4 | 54 | shallow | 49 - 69 | no |

Table 1. Well Depths and Sampling Information.

3.4.2 Groundwater

Groundwater samples will be collected from each well per EII 5.8 Groundwater Sampling (WHC 1988c) and analyzed for the full suite of parameters listed below for the first two rounds of sampling (Section 5.1.6.3 of the 100-FR-3 work plan) (DOE/RL 1991).

3.4.3 Analyses

Samples collected for chemical analysis will be analyzed for the full suite of CERCLA Contract Laboratory Program (CLP) Target Compound List (TCL) and Target Analyte List (TAL) constituents, specific anions that may be present, and for radionuclides. Estimated quantity of material needed for analyses are shown in Tables 1 and 2. The laboratory will use existing Level IV CLP methods and methods approved under their contract for radiological analyses (Level V). Sample custody will follow procedures as outlined in EII 5.1, Chain of Custody (WHC 1988c).

Table 2. List of Analytes (Soil).

| Analyte | Method | Holding Time | Container/Volume |
|--|--------------------------------------|--|--|
| ICP/AA metals Mercury Cyanide | CLP | 6 months 28 days 14 days | G 250 ml |
| VOA | CLP | 14 days | G 125 ml |
| Semi-VOA PCB's/Pesticides Anions Fluoride Nitrate | CLP CLP EPA 300.0 EPA 353.3 | 7 days 1 7 days 28 days 28 days | aG 1000 mi |
| Sulfate | EPA 300.0 | 28 days | |
| Gross alpha Gross beta Gamma spec. Sr-90 C-14 U-235, 238 Pu-239, 240 Am-241 | lab SOP | 6 months | G 1000 mi |
| Total Activity (222-S Lab) | lab SOP | 6 months | G or P small vial (at least 1 gram) |

¹ 7 days for extraction, 40 days after analysis for extraction.

AA = atomic absorber

 \bigcirc

0

CLP = Contract Laboratory Program

ICP = inductively coupled plasma

PCB = polychlorinated biphenyl

N/A = not applicable

SOP = standard operating procedures

VOA = volatile organic analyses

G = glass

aG = amber glass

P = plastic

Table 3. List of Analytes (Groundwater).

| Analyte | Method | Holding Time | Container/Volume |
|--|--------------|---------------------|----------------------------------|
| ICP/AA metals Mercury | CLP | 6 months 28 days | P 3x1000 ml ² |
| Cyanide | CLP | 14 days | P 3X1000 ml ² |
| VOA | CLP | 14 days | Gs 3X40 ml |
| Semi-VOA PCB's/Pesticides | CLP | 7 days ¹ | ag 3x2000 ml ² |
| Anions F, SO | EPA 300.0 | 28 days | P 1000 mt |
| pH Conductivity | 9040 9050 | 28 days | |
| NO ₃ | 353.2 | 28 days | G 500 ml |
| Gross alpha Gross beta Gamma spec. Sr-90 U-235, 238 Pu-239, 240 Am-241 | lab SOP | 6 months | P 6000 ml |
| C-14 | lab SOP | 6 months | P 500 ml |
| Tritium | lab SOP | 6 months | Gs 250 ml |
| Tc-99 | lab SOP | 6 months | P 1000 mi |
| Total Activity | N/A | 6 months | G or P small vial (an least 1 ml |

 $[\]frac{1}{2}$ 7 days for extraction, 40 days after analysis for extraction.

AA = atomic absorber

CLP = Contract Laboratory Program ICP = inductively coupled plasma

PCB = polychiorinated biphenyl

N/A = not applicable

SOP = standard operating procedures

VOA = volatile organic analyses

G = glass

aG = amber glass

P = plastic

If full sample volume requirements cannot be met, the sampling scientist will record the volume obtained in the sampling scientists logbook per EII 1.5, Field Logbooks (WHC 1988c) and analyze in the following order:

- Volatiles
- Semivolatiles/PCB's/pesticides
- 3. Target Analyte List
- 4. Radioisotopes
- Anions
- Total Activity

3.5 GEOPHYSICAL LOGGING

Gross-gamma log all groundwater wells, performing the work in two stages: Stage 1 after completing the first 20 ft of drilling before reducing to a smaller casing. If the gross-gamma tool is not available within 4 h of when needed, skip logging the first 20 ft. Stage 2 after reaching total depth and before completing the well (EII 11.1, Geophysical Logging) (WHC 1988c). Spectral-gamma log groundwater wells only if contamination is indicated by the

^{2 3}X is required for QA/QC in the CLP protocol.

gross-gamma log (survey exceeds 100 cps for any depth interval) or by field screening.

3.6 AQUIFER TESTING

Perform a slug test on each well per Section 5.1.6.2.5 of the 100-FR-3 work plan (DOE/RL 1991) and EII 10.1, Aquifer Testing (WHC 1988c).

4.0 QUALITY ASSURANCE/QUALITY CONTROL REQUIREMENTS

Internal quality control samples shall be collected by the sampling scientist as stated below, per Appendix A, Quality Assurance Project Plan (DOE/RL 1991) and documented in the sampling logbook per EII 1.5, Field Logbooks (WHC 1988c). The trip blank and field blank have been deleted for soil sampling per EPA/540/G-87/004 Appendix C, Section C.6.

Groundwater:

- 1. Collect 1 duplicate for every 10 groundwater samples or a minimum of 1 per reactor area.
- 2. Collect 1 split sample per reactor area.
- 3. Collect field blanks at the same frequency as duplicates.
- 4. Collect 1 (VOA) trip blank per cooler that contains samples that will be analyzed for volatiles. Only analyze for volatiles.
- 5. Collect equipment blanks at the same frequency as duplicates.

Soil:

0

.

~~ \$

S

0

- 1. Collect 1 duplicate for every 20 soil samples.
- 2. Collect 1 split sample per reactor area.
- 3. Field blanks are not required.
- 4. Collect 1 sample each month from any source of water introduced into the hole during drilling. Only 1 sample is required for both groundwater and vadose borings. Analyze for the full suite of water parameters.
- 5. Collect 1 (VOA) trip blank for each batch of containers shipped to the sampling (site) facility and analyze for volatiles only. The media shall be silica sand.
- 6. Collect equipment blanks at the same frequency as duplicates and analyze for the constituents listed in Table 2. The media shall be silica sand.

5.0 SCHEDULE

The following schedule is for drilling in the 100-FR-3 operable unit for 1992. This schedule is subject to change and the operable unit coordinator should be contacted for current status. An Agreement Activity Notification form will be issued at least 5 days prior to start of field work.

| Well number | Drilling dates |
|-------------|---------------------------|
| 199-F6-1 | mid December - late April |
| 199-F5-42 | mid December - late April |
| 199-F5-43A | mid December - late April |
| 199-F5-43B | mid December - late April |
| 199-F5-44 | mīd December - late April |
| 199-F5-46 | mid December - late April |
| 199-F5-45 | mid December - late April |
| 199-F5-48 | mid December - late April |
| 199-F5-47 | mid December - late April |
| 199-F8-3 | mid December - late April |
| 199-F4-1 | mid December - late April |
| 199-F1-2 | mid December - late April |
| 199-F7-3 | mid December - late April |
| 199-F8-4 | mid December - late April |

6.0 CHANGES TO THE DESCRIPTION OF WORK

10

0

9

Major changes to this description of work, such as analyzing different parameters, using different analytical methods, or changing the sampling interval will be submitted on the attached form (Attachment 1) and kept on file with the operable unit coordinator. Copies will be submitted to the lead regulatory agency and appropriate field personnel.

7.0 REFERENCES

- DOE/RL 1991, Remedial Investigation/Feasibility Study Work Plan for the 100-FR-3 Operable Unit, Hanford Site, Richland, Washington, DOE/RL-90-08, U.S. Department of Energy, Richland Field Office, Richland, Washington.
- Taylor, 1991, 100 Area Low Hazard Characterization Activities Safety
 Assessment, WHC-SD-EN-SAD-002, Rev. 0, Westinghouse Hanford Company,
 Richland, Washington.
- WHC, 1987, Industrial Safety Manual, Vol. 1 through 3, WHC-CM-4-3, Westinghouse Hanford Company, Richland, Washington.
- WHC, 1988a, ALARA Program, WHC-CM-4-11, Westinghouse Hanford Company, Richland, Washington.

- WHC, 1988b, Environmental Compliance Manual, WHC-CM-7-5, Westinghouse Hanford Company, Richland, Washington.
- WHC, 1988c, Environmental Investigations and Site Characterization Manual, WHC-CM-7-7, Westinghouse Hanford Company, Richland, Washington.
- WHC, 1988d, *Radiation Protection*, WHC-CM-4-10, Westinghouse Hanford Company, Richland, Washington.
- WHC, 1990, Environmental Engineering, Technology, and Permitting Function Quality Assurance Program Plan, WHC-EP-0383, Westinghouse Hanford Company, Richland, Washington.
- WHC, 1991a, Generic Well Specification, WHC-S-014, Westinghouse Hanford Company, Richland, Washington.
- WHC, 1991b, Health Physics Procedures Manual, WHC-IP-0692, Westinghouse Hanford Company, Richland, Washington.

P-Perfe

()

 \wedge

o∙ ⊘

ATTACHMENT 1

100-FR-3 DESCRIPTION OF WORK PROJECT CHANGE FORM

| Date: | | | | |
|----------------|--------------|------|---------------------------------------|---|
| Person Initiat | ing Change: | | | |
| Change: | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | , |
| | | | | |
| | | | | |
| Reason for Cha | nge: | w su | · · · · · · · · · · · · · · · · · · · | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| APPROVAL: | | | | |
| Field Team Lea | der: | | | |
| | Coordinator: | | | |
| Quality Assura | | | | |

10

N

0

0

DISTRIBUTION SHEET

| To: | From: | Date: |
|---------------|---------------|----------------|
| R. P. Henckel | J. W. Roberts | March 16, 1992 |

Project Title/Work Order:

DESCRIPTION OF WORK FOR THE 100-FR-3 GROUNDWATER OPERABLE UNIT

EDT No.: 157786

ECH No.:

| Name | MSIN | With Attachment | EDT/ECN & Comment | EDT/ECN Only |
|--------------------------|-------|--------------------|----------------------|-----------------|
| G. S. Corrigan | H4-16 | X | | |
| R. E. Day | H4-55 | X | | |
| J. D. Fancher | N3-05 | X | | |
| K. A. Gano | X0-21 | X | | |
| B. A. Gilkeson | L4-78 | X | | |
| E. D. Goller | A5-19 | X | | |
| J. D. Goodenough | A5-19 | X | | |
| A. D. Krug | H4-55 | X | | |
| R. Mabry | X7-02 | x | | |
| D. J. Moak | N3-06 | X | | |
| R. F. Raidl (15 copies) | H4-56 | x | | |
| J. W. Roberts | H4-55 | X | | |
| T. W. Spicer (15 copies) | N3-05 | x | | |
| S. Weiss | H4-55 | X | | |
| S. E. Vukelich | H4-55 | × | | |
| EDMC | H4-22 | x | | |
| Central Files | L4-08 | x | | |
| IRA Clearance | H4-17 | X | | |